



SNUBBER TEST EQUIPMENT

### Barker/ Diacon IPST10 In Place Tester In Place Test Machine

#### Standard Capacities/Performance

##### Lower Ram

Maximum Pressure (activation testing)	12000	psi	810.81	bar
Minimum Flow Rate (Lockup)	10	gpm	37.85	liter/min
Maximum Flow Rate (Bleed)	1	gpm	3.79	liter/min

#### Instrumentation Accuracies

Flow (velocity)	+/- 0.5	% of flowmeter span
Pressure (force)	+/- 0.5	% span

Data Conversion 16 bit

#### Power Requirement

480V/3ph/20A Others available

#### Interconnect Hoses/Cables

Electrical Cables	25	Feet	8	Meters
Main Hydraulic Hoses	50	Feet	15	Meters
Snubber Interconnect Hoses	10	Feet	3	Meters

#### Overall Maximum Size/Weight

24"W x 40" Lx 42" H

#### Weight

500 lbs



IPST10 Snubber Tester